

SPECIFICATIONS:

- 34" x 54" LIFT PLATFORM
- 54" x 54" FOOTPRINT
- 48" HEIGHT
- 23" - 28" LIFT RANGE
- MAXIMUM LOAD 550 lbs [250 kg].
- 8 FEET/MINUTE [2.4 METRES/MINUTE] LIFT SPEED
- SCREW NUT WORM GEAR DRIVE
- MOTOR: 1/2 H.P. 110V A.C.
- POWER SUPPLY: 110V/1PH/60HZ C/W 15A FUSED DISCONNECT
- NON-LOAD BEARING BACKUP SAFETY NUT ON LIFT SHAFT
- SOLID SIDE WALL/HANDRAIL ON CARRIAGE
- ZERO-LOAD START IN BOTTOM POSITION

- ☐ Accepted as Shown
- ☐ Revise and Resubmit
- ☐ Accepted as Modified

Date: _____

Per: _____

APE28PORTABLE-L

NOTES:

- Dimensions are in inches

C	RAM	28/3/18	CHANGE DIMENSIONS FOR 750 DESIGN
B	BH	28/3/06	CORRECT DECK DIMENSIONS

JOB No.	TOTAL TRAVEL	28 [711]	INCHES mm	No. OF LANDINGS	2
LOCATION	PORTABLE TRUS<T>LIFT SAMPLE DRAWING				
ARCHITECT					
GENERAL CONTRACTOR					

FREE OM LiftSystems
by Accessibility Professionals

DWN. BY:

AJK

CHECKED BY:

INSTALLATION DETAILS
AND SPECIFICATIONS


SCALE:
N.T.S.

DATE:
05/07/21


DRAWING No.
52PORTABLE 1/2

REV
C

LOWER LANDING
TOE PLATE



SECTION A-A



PLAN VIEW SECTION

C	RAM	28/3/18	CHANGE DIMENSIONS FOR 750 DESIGN
B	BH	28/3/06	CORRECT DECK DIMENSIONS

JOB No.	TOTAL TRAVEL	28 [711]	INCHES mm	No. OF LANDINGS	2
LOCATION	PORTABLE TRUS<T>LIFT SAMPLE DRAWING				
ARCHITECT					
GENERAL CONTRACTOR					

FREE OMLiftSystems
by Accessibility Professionals

DWN. BY: AJK	INSTALLATION DETAILS AND SPECIFICATIONS			
CHECKED BY:				
SCALE: N.T.S.	DATE: 05/07/21	DRAWING No. 52PORTABLE	2/2	REV C